Contract Communication Collaboration

Erich Tscherteu, Public Utilities Superintendent



Lee County Resource Recovery Facility



Lee County Resource Recovery Facility



Lee County Integrated Waste System

1994

Resource Recovery Campus Opens with Waste-to-Energy plant 1,200 tpd

Scale House

2000 Material Recovery Facility

2003

- Transfer Station
- Yard Waste processing

2007 ► Waste-to-Energy plant expands 1,836 tpd

2010 Fleet Maintenance Facility

2011 ► C & D Recycling Facility

Oversight

LCSW contracts with an engineering firm to oversee plant operations, track data, monitor compliance issues pertaining to contract

- Frequent contact with LCSW management
- Population growth and waste generation 1994-2004
- Plant was at capacity and aging, plant availability was decreasing
- A need for standards of maintenance was identified

Plant Availability 1994 - 2018

New maintenance standards go into effect when third unit is placed in service.



2007 Changes

LCSW created permanent oversight position at WTE

Daily routines include the following:


- Inspection of the facility
- Open discussions with plant management
- Outage planning (mini and major)
- Special projects
- Boiler availability
- Maintenance & Housekeeping Issues

2007 New Approach

Issues concerning MSW intake and processing:

- Cranes
- Parts
- Pit inventory
- Tipping floor capacity and condition
- Ash hauling
- Metals

Boiler Walk-thru (furnace water walls)



Boiler Walk-thru (water wall repairs)



Boiler Walk-thru (boiler roof)



Boiler Walk-thru (feed chute and feed rams)



Boiler walk-thru (back cast tiles vs spray refractory)



Superheater Tubes out for replacement



New superheater tubes overlayed with Inconel



New waterwall tubes with spiral wound Inconel overlay



Generator overhaul every 7 years



Turbine generator overhaul



Turbine rotor



Turbine rotor





Generator overhaul



Generator Internals



Working as a Team

Formal monthly meetings

- Plant Operator
- Contracted Engineering Firm
- Lee County Staff and Management

Formal monthly punch list walk down

- Operations review
- Future plans and projects

Daily Items of discussion

- Safety issues
- Hauler safety staff site visits and observations
- Staffing
- Equipment requirements
- Vendors/Contractors
- Special guests/ VIPs
- Scheduled Tours
- Media Relations
- Training Sessions
- Special Events
- Hauler Appreciation Events

Collaboration Culture

- Open communication with contractors
- ▶ LCSW staff meets daily/weekly to share information pertaining to operations
- Senior management team is kept informed of current issues
- Adapted to a pro-active approach in order to prevent disruptive events
- We strive to deliver excellent customer service to approximately 1,000 customers per day
- Provide a safe disposal environment for all customers, employees and visitors

Incident Collaboration Scenarios

- WTE tipping floor incident -
 - Divert to transfer station?
 - Return at later time?
 - Ship to Lee Hendry Landfill?
- MRF tipping floor capacity issue -
 - Divert to north end of WTE tipping floor?
 - Divert to transfer station, return waste via transfer truck at later time?
- Ferrous/NonFe capacity issues -
 - Divert to transfer station?
 - Provide roll off containers?
 - ► Transfer to landfill for storage, metals returned to facility at later time?
- Yard waste processing or capacity issues -
 - Transfer station or WTE?

Hurricane Irma Sept 10,2017
Cooling Tower contractors were staged a day away in preparation for storm



Immediate clean-up conducted by LCSW & Plant employees



Residue Building Damage Cleanliness of roadways & grounds



WTE Roof Total Loss temporary membrane installed within days



Contact Information



Erich Tscherteu
Lee County Solid Waste
10500-Buckingham Road
Fort Myers Fl 33905
239-533-8931
etscherteu@leegov.com

